

ADDENDUM 2
Nevada Union High School – Pool Building Modernization
11761 Ridge Road, Grass Valley, Ca
Nevada Joint Union High School District

Revisions:

- A. See sheet C1.2, grid coordinates G9, remove existing conifer at west side of Dance Building.
- B. New fencing work surrounding the pool deck, including gates and infills, shall use fence fabric openings sized 1-3/4 inches maximum measured horizontally.
- C. Agreement Form, Article 2, Page 41 of the Project Manual is revised as follows (revised text shown in **bold**):

“... Additionally, the new boiler, filtration, chlorination and mechanical piping for pool heating and chemistry balance, **including all necessary equipment, systems, and controls to provide a fully operational pool system on or before January 18, 2019.**

Clarifications:

- A. For new thresholds referenced on sheet C2.1, note G14, see sheet A7.2, detail D6.
- B. Sheet C2.1. grid coordinates L3, existing low wall and guard rail between new stair and existing building to remain.
- C. Asbestos integral to the boiler to be removed is the responsibility of the District's separate boiler replacement contractor.
- D. There exists a small embedded wood nailer where the existing concrete curbs meet the concrete floor. It is the responsibility of the Contractor to remove this nailer and infill the void with grout/mortar as required to provide a suitable substrate for new interior finish materials. For more information, see the following specification sections:

Execution and Closeout Requirements	01 70 00
Fluid Applied Flooring	09 67 00
Ceramic Tiling	09 30 13

- E. Bid Form, Unit Pricing, page 22 of Project Manual, item “J” unit pricing for replacement of exterior siding shall include any related battens and trim.