

ADDENDUM # 1

To RFP # 18-110

NETWORK EQUIPMENT Cabling Infrastructure

GHIDOTTI HIGH SCHOOL- additional information

NJUHSD eRate Project

PART NUMBER: Ruckus WAP 901-T710-US01 901-R600-US00

WAP Location	IDF Location	Ruckus WAP - Outdoor	Ruckus WAP	Additional Drops
MPOE/MDF	N2			
N2-203 (Learning Center)			1	
N5-Cafe (103)	N5		2	
N6-204	N6		1	
N6-205			1	
N6-206			1	
N6-210 (Admin Office)			1	12
N6-201 (Teacher Room)				4
N6-213 (Teacher Room)				4
N6-Outdoor		1		
N7-214	N7		1	
N7-215			1	
N7-216			1	
N7-205			1	
N7-207			1	
N8-102	N8		1	
N8-103 (Spanish - used occasionally)			1	
N8-108			1	
N8-110 (Teacher Room)				2
N8-112			1	
N8-117			1	
N11-102	N11		1	
N15-100	N15		1	
N15-101			1	

TOTALS: 1 20 22

NJUHSD Internal Connections Cabling Infrastructure RFP #18-110 Site Walk Details

**Distance Estimates in feet include 10 ft service loop at each end of the run
12 strands of General Cable fiber at each location unless otherwise stated**

Nevada Union High School

IDF Location	Pulls to Location	Est. Distance	Notes
E-Wing	Music	320	~Need Panduit LIU w/SC for existing multimode ~May need conduit from E-Wing to Band/Choir Room*
Theater Stage (12)	Music	210	
Music (12)	MPR	170	
MPR (48 - drop 12)	J202	550	
Girl's Gym (48)	J202	610	
Dance (36)	Girls Gym	370	
G3 (24)	Dance	300	Term 12
Wrestling (12)	Pull box outside of Ali Gym	120	
Ali Gym (12)	Pull box outside of Ali Gym	100	
Lower J-Wing (36)	J202	100	Ali pull box to J202 approx = 170 ft
Lib Trans Rm (72)	Lib NOC	150	~Library NOC will need 4u LIU with
Sci Lecture Hall (12)	Lib Trans Rm	140	Added 10ft for running upstairs
S208 (12)	S Wing Pull Box	220	
AG (12)	S Wing Pull Box	220	
District Office (12)	AG	190	TO BE DETERMINED Please add District Office and the DO Modular as option
DO Modular (12)	District office	120	May need conduit work
Auto Classroom	B3	150	Cat6A

North Point Academy

IDF Location	Pulls to Location	Est. Distance	Notes
I-12 (24 - drop 12)	Admin IDF	420	Fusion splice to existing 24 dark strands
I-9 (12)	I-12	110	

Silver Springs High School

IDF Location	Pulls to Location	Est. Distance	Notes
A2 (12)	A5	230	
A5 (24 - drop 12)	Server Room 8	300	
B2 (12)	B1	125	
B1 (24 - drop 12)	Server room 8	500	
Infant center (optional)	Server room 8	320	Outdoor WAP ?
MPOE	Server room 8	170	Replace Cat6 with SM fiber

Ghidotti High School

IDF Location	Pulls to Location	Est. Distance	Notes
5 IDF location - 19 drops		3,000	Cat6A to each WAP Multimode fiber tested and possible re-term Mount WAPs

*District Provided

The due date for this RFP has been changed to **January 18, 2018**.

Vendor to sign as acknowledgment of receipt and return with bid/RFP.

Signature : _____

Date: _____

Company Name (please print) _____